

DOCUMENT 00 91 13 – ADDENDUM

ADDENDUM NO. 2

PROJECT: MCPSA Camp Christi Storage Tank Water System Design
Montgomery County Public Service Authority
755 Roanoke Street
Christiansburg, VA 24073

ENGINEER: Hurt & Proffitt, Inc.
1861 Pratt Drive – Suite 1100, Blacksburg, VA 24060

Receipt of the addendum shall be acknowledged on the bid form. The bidding requirements and Contract Documents and Specifications dated September 30, 2024, for the above project are revised and clarified as listed below.

GENERAL CLARIFICATIONS:

1. The information contained on Plan Sheet G003 applies to the CMU building.
2. The new tank shall have one 24” shell manway.
3. The new tank inlet pipe shall be ductile iron through the floor and then transition to Schedule 80 PVC for the remainder of the run.
4. The overflow pipe for the new tank shall be 12”.
5. The overlow pipe for the new tank shall have a stainless-steel insect screen at the discharge.
6. The new tank does not require an interior ladder.

CONTRACT DOCUMENTS:

Document _____ Modification to be Made: _____


TECHNICAL SPECIFICATIONS:

Section _____ Modification to be Made: _____

DRAWINGS:

Sheet/Detail _____ Modifications to be Made: _____

All other provisions of the contract documents remain unchanged.

Signature  _____
Dennis A. Amos, PE
Vice President

END OF ADDENDUM NO. 2